

## CROSS SECTION OF RIVER DOWN-STREAM

**Name Of Work :- Construction of Submersible Bridge on ON KHERWARA - JAWAS -  
SUVERI ROAD IN KM 9/000, ACROSS RIVER SOM**

## CROSS SECTION OF RIVER AT PROPOSED BRIDGE SITE

HIGHEST FLOOD LEVEL				100.600 M		
Chainage in M (u/s or d/s)	RL in M	DEPTH OF FLOW IN M	LENGTH OF FLOW	AVERAGE DEPTH OF FLOW	CROSS SECTIONAL AREA OF FLOW	WETTED PERIMETER
0	102.000	0.00	0.00	0.00	0.00	0.00
10	100.950	0.00	10.00	0.00	0.00	10.00
20	98.190	2.41	10.00	1.21	12.05	10.29
30	97.590	3.01	10.00	2.71	27.10	10.02
40	97.210	3.39	10.00	3.20	32.00	10.01
50	96.870	3.73	10.00	3.56	35.60	10.01
60	97.960	2.64	10.00	3.19	31.85	10.06
70	97.120	3.48	10.00	3.06	30.60	10.04
80	96.800	3.80	10.00	3.64	36.40	10.01
90	96.470	4.13	10.00	3.97	39.65	10.01
100	96.490	4.11	10.00	4.12	41.20	10.00
110	97.040	3.56	10.00	3.84	38.35	10.02
120	97.290	3.31	10.00	3.44	34.35	10.00
130	97.740	2.86	10.00	3.09	30.85	10.01
140	98.130	2.47	10.00	2.67	26.65	10.01
150	98.850	1.75	10.00	2.11	21.10	10.03
160	98.070	2.53	10.00	2.14	21.40	10.03
170	98.750	1.85	10.00	2.19	21.90	10.02
180	101.850	0.00	10.00	0.92	9.25	10.17
190	102.000	0.00	10.00	0.00	0.00	10.00
		TOTAL	190.00		490.30	190.71

0.00      100.60  
190.00    100.60



